


# Accelerated Bridge Construction




# Accelerated Bridge Construction

New ideas are required to address the dual needs of:


- fast construction
- long service life

# Existing Sections

## Slab Bridge Sections



Voided Slab Girder




Box Girder




# Existing Sections

## Girder Bridge Sections





I-Girder



Bulb Tee Girder


# Existing Sections

## Channel and Double Stemmed Bridge Sections



# Existing Sections

## Girder Diaphragms



Bulb-Tee bridge half diaphragms can be poured at the precast plant and joined together at the site by welding or post-tensioning.

Bulb-Tee diaphragms can also be structural steel X-bracing.




# Precast Concrete Partial Depth Deck Slabs





# Full Depth Bridge Deck Replacement





# Case Studies

Some case studies from Puerto Rico, United States and Canada offer new ideas on **techniques** and **construction details** to achieve the goal of:

Get in.

Get out.

Stay out.

# Baldorioty Bridges, San Juan, PR




- Create Expressway
  - Separate At-Grade Intersections
  - Two Intersections, Four Bridges
- 100,000 ADT

# The Challenge...

- **Design & Build Four Urban Grade Separations**
  - ✿ 2 bridges – 900 ft long x 30'- 4" wide
  - ✿ 2 bridges – 700 ft long x 30'- 4" wide
- **Maintain Continuous Traffic**
- **Complete each Bridge in Less than**

**72 Hours!**





## *Concept*

*Precast adjacent girders*

*Precast cap beam*

*Precast pier*

*CIP footing*



Actual site in dense urban area





Precast pier cap installation





Adjacent  
box girder  
installation





Membrane and asphalt wearing surface

**Baldorioty Bridges, San Juan, PR**



# Completed bridges with traffic



## ***Baldorioty Bridges Construction Report***

- 700-ft Bridge – January 1992 – **36 hours**
- 900-ft Bridge – March 1992 – **21 hours**
- 900-ft Bridge – May 1992 – **23 hours (rain)**
- 700-ft Bridge – July 1992 – **22 hours**

**Ahead of its time – little interest since 1992**



# Cross Bay Boulevard over the North Channel

Jamaica Bay, New York

## Bridge Description

Bridge Length: 2,842 feet, 34 spans, 3 lanes each way plus bicycle lanes, sidewalks and fishing access

## Components used:


- Cylinder piles
- Precast pier cap forms
- Prestressed I-Girders
- Precast diaphragm forms
- Prestressed sub-deck panels
- Precast traffic barriers



Cylinder piles

**Cross Bay Boulevard over North Channel**





Precast pier caps





Pier cap  
construction



## Cross Bay Boulevard over North Channel



## Precast diaphragms



I-girder installation



**Cross Bay Boulevard over North Channel**





Beams in place  
Precast diaphragm forms installed

**Cross Bay Boulevard over North Channel**



Precast deck slab  
placement







Finished bridge

## Cross Bay Boulevard over North Channel



- **Reedy Creek Bridge**

**Disney World** Orlando, Florida


- **The Environment**  
Reedy Creek Wetlands

- **The Need**  
Provide vehicular access to the new  
Animal Kingdom theme park

- **The Solution**  
A precast prestressed concrete slab bridge  
constructed using top down construction




# • Reedy Creek Bridge - Plan




5 continuous segments at 200 ft = 1000 ft  
Each segment = 5 spans at 40 ft

# • Construction Concept - Section





# • Construction Concept - Plan View



# • Cross Section





## • Construction Schedule

- Original Design – cast-in-place construction
- VE proposal used precast components in the same configuration
- The precast alternate saved both cost and time



- **Reedy Creek Bridge**

Deck construction used 405 haunched slabs in two sizes





# • Reedy Creek Bridge

Precast Pile Caps





# • Reedy Creek Bridge





# • Reedy Creek Bridge





# • Reedy Creek Bridge





- **Reedy Creek Bridge**






- **Reedy Creek Bridge**





# • Reedy Creek Bridge



Finished Bridge



# Robert Moses Causeway over Great South Bay

Long Island, NY

South-bound bridge description

Bridge length: approximately 2 miles long  
2 lanes wide, 153 spans

## Components Used

### Original Contract:

- Rehabilitate Superstructure girder and truss spans. Replace 122 stringer spans with spread P/S Box Beams. Replace deck.

### VE Proposal:

- Substitute full-width quad-Tee span segments for spread box-girder spans.





Quad-Tee full width  
deck segments  
at the precast plant







Robert Moses Causeway over Great South Bay



Finished bridge



# MOOSE CREEK BRIDGE

Total Precast Concrete Bridge Structure  
Near Timmins, Ontario





Summer 2004

Owner: MTO - Engineer: Stantec Consulting  
Contractor: Miller Paving - Precast: Pre-Con Inc.




# Precast Elements

- Precast Superstructure:
  - 6 CPCI 1200 I-girders precast with a monolithic deck




# Precast Elements

- Precast Substructure:
  - 10 Abutment Elements
    - 3 Stem units per abutment
    - 2 Wingwall units per abutment




Precast Stem & Wingwall Plan (Hatched Area-CIP Concrete)






2 DIMENSION  
1 : 25




2 REINFORCEMENT  
1 : 25





3 REINFORCEMENT  
1 : 25

## Deck Girder Details




DETAIL 'A'  
1 : 5

DETAIL 'B'  
1 : 5



DETAIL 'A'  
1 : 10



DETAIL 'B'  
1 : 2

## Deck Joint Details

# Girder/Deck Production

- Units were prestressed and conventionally reinforced - similar to typical CPCI girders...





# Girder/Deck Production

- ...with the bridge deck cast monolithically on top



Wood forms were used for these prototype deck girders

# Girder/Deck Production

- The girder deck was formed with a parabolic shape in elevation and cross slope in section to account for camber and cross fall





# Stem/Wingwall Installation

- Precast was erected in two mobilizations; first - stems and wingwalls beginning July 28/04
- Stem and wingwall units were shipped flat



# Stem/Wingwall Installation

- Steel piles and HSS knee bracing system were installed by the General Contractor





# Stem/Wingwall Installation

- System also acted as temporary lateral support for abutment stem units



# Stem/Wingwall Installation

- For stability, the outer abutment stem units were erected first...





# Stem/Wingwall Installation

- Wingwall is set on a steel pile...



# Stem/Wingwall Installation

- Wingwall end reinforcing is threaded through the reinforcing of the end stem units



Side View



End View



# Stem/Wingwall Installation

- Installation of the stem and wingwall units took place over two days
- Cast-in-place bearing seats and closure strips between stem units was cast by Contractor after installation complete
- Lateral bracing was removed when concrete reached minimum strength



# Girder/Deck Installation

- The deck girders were erected 3 weeks after the stem and wingwalls, on August 19/04





# Girder/Deck Installation

- Girders were erected from a temporary bridge adjacent to the site



# Girder/Deck Installation

- Middle girders were placed first and braced temporarily to the stem unit for stability before adding the permanent steel diaphragms





# Girder/Deck Installation

- Installation continued outwards until complete
- Bracing from middle unit to stem was then removed



# Girder/Deck Installation

- Girder installation progressed quickly and was completed within one day





# Moose Creek Bridge Opening

The bridge opened to traffic on October 27, 2004



# Davis Narrows Bridge

Brooksville-Penobscot, ME



## Precast Components

- 4 abutments
- 4 wing walls
- 8 box girders
- 4 approach slabs

Designer/Owner: Maine DOT

General Contractor: Reed & Reed Inc.

Precaster: Strescon Limited, Saint John, NB



# Abutments and Wing Walls



Davis Narrows Bridge



# Abutments and Wing Walls



Transverse  
Post-tensioning





# Box Girder Erection





# Box Girders



## 8 GIRDERS

27.1 m (89 ft) long

1220 mm (4 ft) wide

915 mm (3 ft) deep

Weight 45 t





# Approach slab installation





# Bridge Deck Membrane





# Bridge Deck Paving



- Project was finished with only one month of road closure.

# The Faster the Better

Projects such as the Moose Creek and Davis Narrows Bridges are part of a North American initiative - looking at ways to speed up bridge construction to minimize costs and inconvenience to the public.

## ISSUES

- Collaboration
- Pricing
- Standard Sections
- Future Markets
- Constructability
- Tolerances
- Research



# Conclusions



- The structural precast concrete industry has extensive knowledge and over 50 years of experience in the manufacturing, delivery and installation of precast bridge components.

- The industry is ready and willing to work with ministries of transport, bridge consultants and contractors under certain conditions:

# Conclusions

- Standard tender methods are not conducive to innovative solutions. In many cases, precast manufacturers are reluctant to share their expertise and ideas with others prior to bidding.
- As voluntary alternates are not considered unless the contractor is the low bidder, new ideas and value engineering may not be worth the risk or effort. *The precaster generally has no access to the designer during the tender period to answer technical questions.*



# Conclusions

- Require that precast concrete elements, manufactured in precast plants, be certified in accordance with CSA Standard A23.4 and provincial standards prior to tenders being issued.
- This will prevent the possibility of poor or unacceptable results due to unqualified fabricators.
- CPCI members have access to the latest bridge design and technology throughout North America. *In some cases the Contractors are encouraged to bid the precast work - placing the precast industry in a situation where they are supplying their tendered number and ideas directly to their competition.*

# Conclusions

- Standard bridge details should be revised or relaxed if they become barriers to innovation and new ways of construction.
- Use large precast components to speed up the construction.
- *Consult with precast manufacturers regarding constructability, shippable sizes and weights and erection equipment required to install the large pieces at the jobsite.*



# Conclusions

- Industry standard tolerances are given in CSA Standard A23.4.
- Do not require unnecessary tolerances.
- Design details that can accommodate the length and out-of-square tolerances in large precast members.
- *New sections, if developed, need standard tolerances as their camber behavior is only theoretical.*

# Conclusions

- Construction management contracts should be used, initially on a trial basis, to team all trades including precast contractors with forward looking engineers to find new ways to accelerate construction without sacrificing the design life of structures. *The quality control in certified precast plants can be used to everyone's advantage.*
- If the idea is to speed up construction, put a value on the reduced time and require guaranteed schedules.



# Conclusions

- Scope and contracts should be performance related and clearly outline all functional requirements of a structure.
- Don't be afraid to try new ideas. Keep an open mind. Not everything will work as expected. Some ideas will exceed expectation.
- *There has to be a reward to promote innovation and incur risk.*

# Conclusions

## PROTOTYPES

- Use prototypes to try out new techniques on a smaller scale.
- Be prepared to pay a premium for these trials.
- *If the prototypes are successful and/or require modifications, proper tooling up and formwork can be purchased when these prototypes become standard construction methods for future projects.*



# Thank you



**Canadian Precast/Prestressed Concrete Institute**

**Web: [www.cpci.ca](http://www.cpci.ca)**

**CPCI members: [www.precastsearch.com](http://www.precastsearch.com)**

**CPCI email: [info@cpci.ca](mailto:info@cpci.ca)**

**Call toll free: [1-877-937-2724](tel:1-877-937-2724)**